BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18407/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22-01-2016

Removal of Debris and Berm Cutting in KNV 1st Stage, 2nd Stage, Pillegowda Layout, Ramachanrapura Old Village, Bloom Moon Garden, Hanumaan Layout in ward no 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M D SRINIVASA		
				In Figures		In Words
1	1011.15	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	80.65	81549.25	Rupees Eighty and Sixty Five Paise Only
2	1155.6	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance	Cum	155.04	179164.22	Rupees One Hundred Fifty Five and Four Paise Only
3	2166.75	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	103.15	223500.26	Rupees One Hundred Three and Fifteen Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/02

26/1/16